Now In Production



VA Hospital, located in Wood, WI

A 100% make up air multi-zone unit with 55 Tons of DX cooling, and hot water heating section to replace an existing Govrenair unit with a service corridor.

Representative: Milwaukee Trane Co. 11400 W. Theodore Trecker Way, W. Allis, WI 53214 Jim Steele P 414-266-5200; F 414-266-5216

4 scroll compressors and 12 rows of evaporator coils will condition 7,800 CFM of fresh air from 95 / 78 deg. F to 47.4 / 47.3 deg F discharge air temperature. Condensing section EER 13.1 and total unit EER 10.3.



Replacement double deck multi-zone with service corridor.



Pre-heat hot water coil with face and bypass dampers and a hot water coil in the hot deck.



Steam humidifier, 30% pleated and 85% bag filters



Oversized condenser surface with energy efficient condenser fan motors



Now In Production



VA Hospital, located in Wood, WI

A 100% make up air multi-zone unit with 55 Tons of DX cooling, and hot water coil heat section to replace an existing Govrenair unit with a side corridor.

Representative: Milwaukee Trane Co. 11400 W. Theodore Trecker Way, W. Allis, WI 53214 Jim Steele P 414-266-5200; F 414-266-5216

682,527 btuh cooling 320,318 btuh hot water heating 222 LB/HR steam humidifier.





Painted aluminum exterior panels and expanded aluminum condenser coil guards.





Service corridor with hinged access doors, single door handle with multiple latches, aluminum tread plate floor, exhaust fan and electric heater.

